GOVERNMENT OF MYSORE, ELECTRICAL DEPARTMENT.

OFFICE OF THE SUPERINTENDING ENGINEER, ELECTRICAL DEPARTMENT, BANGALORE.

Notification dated 8th of July 1938.

Notice is hereby given that sealed tenders will be received at the Office of the Superintending Engineer, Electrical Department, Bangalore, up to 3 P.M. on the 30th July 1938 for constructing one block of five Linemen's quarters with latrines at Harihar Town. An approximate estimate of quantities is given below. These quantities are not guaranteed. The works should be completed by the end of September 1938.

2. The plans, detailed estimate and conditions may be seen at the Office of the Superintending Engineer, Electrical Department, Bangalore, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms, which may be obtained from the Superintending Engineer. The Tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 200 in cash or Government promissory notes, as earnest money, and be superscribed "Tender for constructing Linemen's quarters at Harihar Town", in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted will be pasted on to the Notice Board in the Superintending Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Public Works Department or those fixed by the Superintending Engineer, after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of disputes about rates, quantities measurements, quality of work, etc., and in all disputes of any kind, the decision of the Superintending Engineer, will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

13 Charges on account of water, scaffolding materials implements for setting out, barricading, clearing site, supply of work, etc., that may be found necessary during execution will not be paid for separately, but should be borne by the contractor.

Constructing a Block of Five Linemen's Quarters at Harihar Town.

Item No.	Description of work	Unit	Rate	Quantity	Rates to be quoted
			Rs. a. p.		
1	Earthwork excavation and filling in basement	C.yd.	0 3 0	36	
2	Concrete stone jelly in lime mortar	C.ft.	0 4 0	374	
3	Size stone in clay foundation and basement with bond stones, as per specifications ..	,,	0 3 6	928	
4	Burnt brick in clay superstructure.	,,	0 3 3	2,078	
5	Burnt brick in mortar	,,	0 4 6	691	
6	Stone slabs 4" thick, rough dressed and fixed in mortar	S.ft.	0 8 0	195	
7	Chunam plastering	Sqrs.	3 4 0	56·00	
8	Cement pointing with thread lines	,,	4 4 0	1·53	
9	White and colour washing, two coats ..	,,	0 4 0	57·53	
10	Roofing with first class Mangalore tiles over T.W. reepers 2"×1" including wood oiling.	,,	26 0 0	19·64	
11	Ridge tiles set in mortar, and cement pointed	R.ft.	0 8 0	86	
12	Ventilating tiles fixed complete	No.	2 0 0	20	
13	T.W. wrought and put up, including two coats of wood oiling	C.ft.	6 0 0	77·39	
14	T.W. doors battened, 1" thick, shutters, with iron fixtures complete, as per drawing ..	S.ft.	1 4 0	195	
15	T.W. battened windows with 1" thick shutters and $\frac{5}{8}$" dia. iron bars, with iron fixtures complete as per drawing	,,	1 8 0	90	

Item No.	Description of work	Unit	Rate	Quantity	Rates to be quoted
			Rs. a. p.		
16	T.W. shelves with frames and shutters, &c., complete	,,	1 0 0	75	
17	Chocolate painting, two coats	Sqr.	3 8 0	8·40	
18	Constructing sinks	No.	3 0 0	5	
19	Providing stone mortar and pestle complete, fixed	,,	5 0 0	5	
20	Flooring with 3" lime concrete 1½" cement concrete and cement plaster on top, &c., complete	Sqrs.	20 0 0	10·00	
21	Levelling ground	L.S.		Item	

Constructing One Unit of Latrine at Harihar.

Item No.	Description	Unit	Rate	Quantity	Rates to be quoted
			Rs. a. p.		
1	Earthwork excavation for foundation	C.yd.	0 3 0	4	
2	Stone in mortar foundations and basement	C.ft.	0 5 0	130	
3	Burnt brick in mortar superstructure	,,	0 4 6	193	
4	Chunam plastering, two coats	Sqr.	3 4 0	4·91	
5	Cement pointing with thread lines	,,	4 4 0	0·56	
6	White and colour washing, two coats	,,	0 4 0	5·47	
7	Cement plastering ½" thick	,,	8 0 0	0·80	
8	Tar washing, two coats	,,	2 8 0	0·63	
9	Flooring with 3" concrete 1" cement concrete and plaster ½" thick in cement	,,	20 0 0	0·38	
10	Fixing outlets and constructing drains	L.S.	10 0 0	Item	
11	Providing galvanised iron sheet tubs 12"×6" complete with tarring	Each	0 12 0	6	

L. A. H. WINCKLER,
Superintending Engineer.

OFFICE OF THE SUPERINTENDENT, POWER & LIGHT, MYSORE.

Notification dated the 7th July 1938.

Sealed tenders in triplicate will be received at the Office of the Superintendent, Power and Lighting, Mysore, superscribed with the name of the work mentioned below.

2. The plans connected with the work may be seen at the Office of the undersigned at all working hours. The copies if required will be made available on payment of Rs. 3 per set.

3. The tenders should be drawn up strictly in accordance with the specifications furnished, at the same time writing out the rates at which each item of work is executed in figures as well as in words, failing which no cognisance is taken of the tender. No items other than those noted in the statement should be included in the tender as the items include provision for all sundries, repairs to damaged masonry and painting the casings, boards lead cables, etc.

4. The materials to be used on the work should be of best manufacture conforming to the departmental wiring rules and the latest B. S. or A. I. E. E. specifications and mention should clearly be made of the manufacture and catalogue numbers of the materials offered. The T. W. planks, etc., to be used in the work should be well seasoned and free from cracks knots and white wood. The minimum width of the plank to be used to boards, etc., should not be less than 12 inches unless it is to make up the difference in size of the board required. In all cases lap joints should be adopted. In no case joints would be permitted to be put up diagonally for the boards.

5. The undersigned reserves the right to reject the tenders without assigning any reasons therefor.

6. The successful tenderer will be required to deposit an earnest money of Rs. 50 (Rs. fifty) and Rs. 45 (Rs. forty-five) on each of the works in cash and execute an agreement within a week from the date of intimation as to the acceptance of the tender, failing which the tender will be disposed of otherwise at his risk.

7. In executing the work, the wiring rules of this Department as well as those of the Institution of Electrical Engineers should be strictly followed.